

LMC Refurbishment

Room	List of works
Green Room	<ul style="list-style-type: none"> • Lighting to be dimmable (removal of fairy lights) (Lighting has already been improved to warm LED) • Removal of wall strip light • More electrical sockets around the room and moved up to waist height, to include USB charging points • Replace sink • Remove hot water tap (including boiler box) so sink only provides cold water, or replace boiler box with better/safer box • Creation of storage area and tea and coffee self service area around sink • Plastering of walls, 9mm plasterboard to assist with sound proofing the room and painting in neutral tones • White boards and pin boards around the room, some magnetic • Replace curtains with blinds • Install door releases (e.g. Dorguard)
Heather Room	<p>As per Green Room plus:</p> <ul style="list-style-type: none"> • Replace lighting with dimmable warm LED lighting • Move CAB cabinets upstairs out of the room
Canada Room	<ul style="list-style-type: none"> • Dimmable and sectionalised LED square warm lights (like Green Room) and remove fairy lights • Replace ceiling tiles with similar to current tiles • Replace carpet with grey carpet tiles (like in the office) • Replace curtains with blinds • Replace Dorguard door closers with overhead closers